PILLAR&ROOF(RCC)-TisconSD-RODS-SPECIFICATION(4-MCBexternalBOXES-AtStaircaseCorridorWall-GndFloor)

- TATA-TisconSD(Exact-Specification):TisconSD(Fe-500SD, MYS520), [MYS is MinimumYieldStrength of 520, SD is SUPER-DUCTILE, Fe is symbol for IRON]
- 10MM LONG-LENGTH, if-required CROSS-Concealed-BEAM-HavingWidth9Inch-Thickness(Height)4Inch-Every-10 feet.
- 3. CROSS-CONCEALED-BEAM will not be needed in case of HOME28.
- ((CONCEALED-BEAM)/(CROSS-CONCEALED-BEAM))-12MM(6MM-Rectangular-RINGS)
- 5. 12MM SHORT-LENGTH
- 6. 6-PILLARS 16MM(8MM-Rectangular-RINGS).
- 7. Though PILLARS are 18Inchesx10.5Inches, for-concrete-mixture-margin, PILLARS are [17Inchesx9.5Inches::outerRING-To-outerRING-(R2R)]. This will give 0.5Inch Concrete-mixture-margin-on-all-sides.
- 8. BALCONY1 & BALCONY2, PROJECTION, 20FEET-CONCEALED-BEAM-14MM (On-two-9Inch-Walls)
- $9. \hspace{0.5cm} \textbf{Extend-Forward-the-Two-9Inch-Walls-Full-Height-All-Floors-Till-Front-Boundary}. \\$
- 10. 12FEET6INCHES-CONCEALED-BEAM-16MM(on-front-inner-DrawingRoomStaircase-4.5Inch-Wall)[AND]8FEET1.5INCH ES-CONCEALED-BEAM-16MM(on-rear-inner-BedRoomBathroom-4.5Inch-Wall).
- 11. BALCONY1 & BALCONY2 OutermostEdge15feetCONCEALEDBEAM12MM
- 12. REAR-END-4.5InchWALL CONCEALED-BEAM-12MM-AT-EveryFLOOR.
- 13. ROOF(RCC)-THICKNESS-5.5INCH
- 14. For PILLARS,

TisconSD-Rods-Iron-Grid-BaseStand-Lifted-Gap2Inch-From-UNIFORMLY-PRESSED-LEVELLED-3InchThickHammered Brick.GapLift-by-placingBelow(grid/gridJoints)small-sufficient-brick-Pieces

- 15. For ROOF(RCC)
  - TisconSD-Rods-Iron-Grid-LiftedGap-0.5Inch-From-ShatteringSurface(i.e.At-All-NON-Cantilever-Places).GapLift-by-placin g-Below(grid/grid/Joints)-small-sufficient-brick-Pieces.
- 16. All-CONCEALED-BEAMS-LiftedGap-from-(Wall/ShatteringSurface)-by-0.5Inch.GapLift-by-placing-Below(grid/gridJoints)-s mall-sufficient-brick-Pieces.(0.5Inch-LiftedGap-At-All-Places-of-CantileversBottomLevelRods).
- 17. For ROOF(RCC), TisconSD-RODS GRID-INTERSPACING-5Inches.
- 18. (2.5FEET/1.5FEET/1 FEET)-LENGTH-CANTILEVER-RODS-GRID-on(from)-all-4.5Inch-aswellas-9Inch-WALLS.
- a) Along-Two-9InchWalls-1.5feetCantilever(perpendicular)///(b)Along-15feet4.5InchWallFront-2.5feet-Cantilever(perpendicular)///(c)Along-15feet4.5InchWallRear-2.5feet-Cantilever(perpendicular)///(d)Along-15feet4.5InchWallMiddle-BothSides-1.5feet-Cantilever(perpendicular)///(e)Along-KitchenInner4.5InchWall-BothSides-1feet-Cantilever(perpendicular)///(f)Along-DrawingRoomStaircase4.5InchWall-BothSides-1feet-Cantilever(perpendicular)///(g)Along-BedroomBathroom4.5InchWall-BothSides-1.5feetCantilever(perpendicular)
- 19. CONCEALED-BEAM-THICKNESS(Height)-outerRING-To-outerRING-(R2R)-4Inches.
- 20. CANTILEVER-THICKNESS(Height)-should-be-made-Equal-To-CONCEALED-BEAM-THICKNESS(Height)-4Inches.
- 21. CONCEALED-BEAM-WIDTH-IS-WALL-WIDTH(4.5(4)Inches or 9Inches)-(R2R), as-per-Wall.
- 22. Though DRAWING-ROOM front-4.5Inch-Wall-has-a-Slanted-Corner, but-CONCEALED-BEAM-12MM is-Straight-15FEET. Also, BEDROOM Front-Door-Wall aswellas REAR-DOOR-Wall have 15FEET-CONCEALED-BEAM-12MM.
- 23. WHERE,RoofCeiling(Kitchen&WashingMachineArea&BathroomcumToilet) is DOWN the ConcealedBeamHEIGHT(onPlacesofJointWalls)isINCREASED-to-bring-it-at-the-Same-Level-as-that-of-adjoiningRoom.B UT,CantileverThickness(Height)is-as-before, i.e.3Inches.
- 24. KITCHEN-SLAB-there-will-be-one-middle-supporting-wall.SLAB-THICKNESS3Inches[At-Height(2feet6Inch+3InchesSlab)]
- 25. Bathroom-cum-Toilet-EXHAUST\_FAN
  - is-installed OVER-Vertical-Sliding Window-on-one-side-opposite-to-C is term (not-at-center).
- 26. GITTI(StoneGravel)-SIZE-1inch(25.4mm)should NOT have (Orange/Yellow/PaleYellow) TINGE.
- 27. JEERA-GITTI(StoneGravel)-SIZE-8mm.
- 28. BELTECNO-SS-Bolted-WaterTANK.
  - On&Over-the-multiple-concreteMixture-TisconSD-8mmRodsGrid-Slabs1feetBreadth3InchThick(KeptTransverseAlongTan kLengthOverBrickWalls), the DrawingRoomTankAreaFloor should have 3InchThickWOOD-BOARD(KITPLY-BWP-KITBOARD-GOLD-25mm(1inch)Thick-3PiecesFevicol-Joined-To-Increase-Thic kness),LiftableBoardpainted-inColorofDrawingRoomTile
- If greater SPACE is REQUIRED, take foundationSTART of KitchenDrawingRoomWall to be
  [9Inch(1Brick)/13.5Inch(1.5Brick)], Instead of 18Inch(2Bricks), taking into CONSIDERATION
  the(BREADTH&overallRequiredDEPTH)-of-BELTECNO-SS-Bolted-WaterTank-AlongWithTwo-4.5InchBrickWallsAlongTa
  nkLengthCASINGforWaterTank.But,theKitchenDrawingRoom-INTERIOR-SIDE-4.5InchWallFoundationStartis-as-before18
  Inch(2Bricks)
- ELECTRICIAN is called for PVC pipes Laying(for-ElectricalWires-FanCeilingBrackets),
   AFTER-TisconSD-Rods-ConcealedBeam-Laving-Work-is-finished-&-BeforeConcreteMixtureWork.
- KITCHEN9inchWall2-25AmpSockets&4-6Asockets,BATHRoom-cum-Toilet1-16Asocket&1-6Askt,WASHm/c1-6Askt,DRA WINGRoom2-25Asockets(Fridge,Computer-cum-TV)&4-6Asockets(2EachOn2Walls),BEDRoom2-25Asockets&3-6Asocket tOneEachOnNonWindowWalls.GENERATOR-ConnectionTo-ONE-25A-SocketIn-Kitchen&BedroomStudy&DrawingRoom, Legrand-ARTEOR:SwichedSkt25A-5738-10,SwitchedSkt16A-5735-10,Skt6A-5734-71. Internal-Wall-Bracket-for-Sockets.